

**La Plata Archuleta Water District
Phase 2C Water Distribution System Project
Bid and Contract Documents:**

Addendum No. 2

March 25, 2024

This Addendum of the LAPLAWD Phase 2C Water Distribution System Project is hereby issued as follows:

1. The following clarifications have been requested:
 - a. In the event the bottom of the trench is too wet and muddy to support the pipe, Item 13 of the Schedule of Values provides for Trench Stabilization.
 - b. Temporary Easements have been obtained from adjacent land owners for bores under County roads.
 - c. There is not a normal groundwater table, but some groundwater may be encountered due to adjacent irrigated farmland. It is anticipated that any groundwater can be handled by a standard 2-inch mud pump.
 - d. There are no changes to General Notes G, H or I on the Drawings.
 - e. There is no survey control on-site.
 - f. Wetland areas are delineated by a solid green line. The hatching as indicated on the legend is difficult to see on the drawings.
 - g. The annulus between the casing and carrier pipe does not need to be filled with sand.
 - h. Class 6 ABC in 12-inch lifts compacted to 95% is an option to flowfill only as it applies to Note G. Open cuts of the County road will require flowfill with the top 8-inches compacted Class 6 ABC.
 - i. The District does not have a crew that applies mag chloride. The Contractor will need to locate their own source for mag chloride.
2. Regarding post-trenching refill and associated trench compaction testing, the District will procure the services of a geotechnical firm to provide soils and compaction testing for the project.
3. The District will provide alignment for the pipeline (see drawings). Contractor shall provide staking of easements, with District provided easement descriptions.
4. Replace the existing Acknowledgement of Web Delivered Documents with the Attached.

End

ACKNOWLEDGEMENT OF WEB DELIVERED DOCUMENTS

THE FOLLOWING DOCUMENTS WERE AVAILABLE, ON THE LA PLATA ARCHULETA DISTRICT WEBSITE, FOR REVIEW IN PREPARING THIS BID PROPOSAL AT LEAST 5 DAYS PRIOR TO THE BID OPENING:

Exhibit A

1. *Project Map (Cover Sheet of the Project Drawings)*
2. *Bid Schedule (Page 32 of these Contract Documents), dated 2/28/2024.*
3. *The Project Drawings (Sheets 2 through 21) and Standard Details dated 2/28/2024.*

Miscellaneous

4. *These Contract Documents, including web access to the Standard Specifications, Division I and II, dated June 6, 2020*
5. *Clarification #1, Dated 2-29-24*
6. *Addendum #1, Dated 3-1-24*
7. *Addendum #2, Dated 3-25-24*

The Bid Schedule of Values provided for the La Plata Archuleta Water District Phase 2C Pipeline Project is an estimation of required elements and amounts for completion of this project. Quantities listed are approximate and may not represent actual amounts. Contractor shall be responsible for ascertaining actual installed quantities as shown on the project plans and as verified by the Contractor's own field inspection. Locations of other utilities are approximate and may not be complete or correct; Contractor is responsible for all utility locates and coordination and will notify Owner for approval of any associated Project changes required.

All of these items were provided for review on the laplawd.org website and were utilized in the development of this proposal.

Acknowledged On _____, 2024.

By: _____
(Bidder)